BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the **Work : Desilting and debris clearance in main and cross road drains in Bhadrappa layout, devinagara, lottegollahalli, muneshwaranagara, tatanagara, kodigehalli and surroundings areas in ward no. 8, Kodigehalli**

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	1767.80	Excavation and removal of silt and silt mix with sand in slushy condition form canal bed including disposing of the same in spoil bank or on canal embankment inlaysers as directed etc., complete with an initial lead upto 50	cum	243.12	
2	2507.40	Removing B.S Slab of Drain and stacking including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	sqm	63.72	
3	2507.40	Refixing stone slabs of drains and pointing in C.M (1:3) including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	sqm	78.84	

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

21/12/15

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore